

Amendment

Annexure-I

BILL OF QUANTITIES

Sl.No.	Description of Work	Qty. (No's/ mtrs)	Unit (No's/ mtrs)	Estimated Cost		Amount
				In figure (Rs.)	In Words	
BOQ FOR NETWORKING						
1	Supply and Laying of CAT6 Cable (mtrs)	18000	mtrs			
2	Supply and fixing of I/O boxes with RJ11 and RJ45 Connectors (no's)	800	No's			
3	Supply and fixing of CAT6 UTP information outlet (no's)	800	No's			
4	Supply of CAT6 UTP Patch Card (4 ft)	600	No's			
5	Supply of CAT6 UTP Patch Card (7ft)	200	No's			
6	Supply and fixing of 24 port Jack Patch Panel Straight (no's)	50	No's			
7	Supply and fixing of 24 Port Switches (Managed)	15	No's			
8	Supply and fixing of 24 Port Switches (Unmanaged)	35	No's			
9	Supply and fixing of 12U Wall mount Rack	30	No's			
10	Supply and Laying of 12 Core Single mode fiber cable	1500	mtrs			
11	Supply and fixing of 24 Port LIU with coupler & Adapter	1	No's			
12	Supply and fixing of 12 Port LIU with coupler & Adapter	7	No's			
13	Supply and fixing of SC-LC Type	20	No's			

	fiber Patch Cord (5mtrs)					
14	Supply and fixing of Sc Type Pigtail Single Mode	35	No's			
15	Supply and Laying of 1.5" PVC Pipe with accessories	4000	mtrs			
16	Splicing of Pigtail	30	No's			
17	Construction of Network Trench Height X Depth (1ft X 1ft)	250	No's			
18	Supply and Laying of 1" HDPE Pipe(PE 80 or 100, Thickness 2MM, Smooth Inner Surface)	1000	mtrs			

BOQ FOR INTERCOM						
1	Supply and Configurations of NEC SL 1000 model Expansion Bin with 8Trks and 64Extns (should be support)	1	No's			
2	Supply and fixing of Caller ID Telephone	150	No's			
3	Supply & Laying of 50P JF UG cable	800	mtrs			
4	Supply & Laying of 20P JF UG cable	500	mtrs			
5	Supply & Laying of 50P Distribution Box	8	No's			
6	Supply & Laying of 20P Distribution Box	3	No's			
7	Supply & Laying of 2 Pair (.51mm) Telephone cable	8000	mtrs			